








Roof pitch 18° roof tiles on 38x38mm Battens spaced @ 345mm max. c/cs on isolation. 2 X M12 bolts at heel and splice joints.
Inumber x type) top chord 114mm grade 5, bottom chord 114mm grade 5 & web 114mm grade 5 in size & grade in accordance with spans 1782-2. L bays required within a span of 6000mm Timber King Post Truss & Truss spacing @ 760 c/c 1650 where slates or tiles have a self mass in excess of 55kg/m². BMI coverland underlie membrane to be placed as dump proof underlay All trusses to be tied down over 114x38mm wallplates by means of 32x2mm galv. hoop iron straps embedded 600mm min. into Brickwork. All timber to be CLASS A, GRADE 5 as required by NBR: spans 10400.

G.I Sheets at 5' pitch on purlins
75X50mm at 900 spacing on
152x50mm rafters at 900mm spacing
attached by hurricane ties on
228X38mm bearer beam fixed on
100mmØ steel posts by means of
metal connectors. All timber to be CLASS A,
GRADE 7 as required by NBR- sabs. 10400



- Max. Span 3000mm, Pre-cast to approval 4 courses of brickwork with brickforce above the lintol. Greater spans to be in R.I.conc.
- Pre-cast lintols to extend min 230mm beyond openings
- Lintols to be Laid in accordance with manufacturers specifications.



BOX GUTTER DETAIL



SITE AND GROUND FLOOR PLAN
scale 1:100

DULLES ROAD

AREA	CALCULATIONS
AREA OF SITE	= 266.11sqm.
EX-GROUND FLOOR	= 36.17sqm
GROUND FLOOR EXTENSION	= 48.19 sqm
CARPORIT	= 64.67 sqm
TOTAL COVERAGE	= 149.03sqm
PERCENTAGE COVERAGE	56.00 %

LINEAR CALCULATIONS

TOTAL LINEAR DISTANCE :	AB(11.00)+BC(11.50)+CD(11.00)	= 33.50m
TOTAL ALLOWED 60% LINEAR COVERAGE :		=20.10
TOTAL BUILDING COVERAGE :	DE(6.99)+FA(6.99)	= 13.98M
TOTAL % LINEAR COVERAGE :		= 41.73 %

FENESTRATION ENTIRE GROUND FLOOR & NEW EXTENSION		
TOTAL FLOOR AREA	=	75.32sqm
15%	=	11.29sqm
GLAZING	=	11.16sqm
THUS		14.81%


FENESTRATION MASTERS BEDROOM		
TOTAL FLOOR AREA	=	10.41sqm
15%	=	1.56sqm
GLAZING	=	1.44sqm
THUS		13.83%

- ALL RAINWATER PIPE TO FREE DISCHARGE TO THE YARD

NOTE:
ALL WINDOWS & DOORS NOT TO
ERECTED LESS THAN 1.0M AWAY FROM
BOUNDARY

ROOF & CEILING PROFILE R-VALUE COMPLIANCE WITH SANS 204 ZONE 4 PROPOSED EXTENSION		
ROOF PROFILE	COMPONENT	R-VALUE
	Non-ventilated upward flow.	
GALVANISED ROOF SHEETS (75kg/m ²)	*Metal * Outdoor Air Film	0.03 0.18
Branding @ 345mm c/c	*Roof Air Space Sissilation from 430 reflective foil .ie radiant Vapor barrier	0.68
	*Indoor Air Film- Still Air Ceiling Insulation, 135mm	0.11
	*Thick Aerulite Ceiling Insulation	3.38
	*10mm Rhino Board Firestop Ceiling	0.06
TOTAL R-VALUE OF ROOF		4.44 m2 KW
For ventilation spaces, the ventilation should not be less than 0.5L/s m2		
Permissible R-Value		3.70 M2 KW
	Component	R-Value
HotWater pipes	Insoler Aerolite 135mm dia Snap on Glasswool Pipe section insulation	1.00
TOTAL R-VALUE OF ROOF		1.00 m2 KW
All Exposed hot water pipes with a 80mm dia. Must be insulated with a minimum R-Value of 1.00 m2 KW		
All Exposed hot water pipes with a dia. Greater than 80 mm dia. Must be insulated with a Minimum R-Value of 1.5 m2 kW		

ROOF & CEILING PROFILE R-VALUE COMPLIANCE WITH SANS 204		
ZONE 4		P_1
ROOF PROFILE	COMPONENT	R-VALUE
	Non-ventilated upward flow.	
Concrete Roof Tiles (17.5mm R10m)	*Coverland Cement Roof Tiles *Quikrete Air Film	0.02 0.18
Branding @ 345mm c/c	*Roof Air Space Stilation from 430 reflective foil. i.e. radiant Vapor barrier *Indoor Air Film- Still Air Ceiling Insulation, 135mm *Thick Aeroflex Ceiling insulation *10mm Rhino Board Firestop Ceiling	0.08 0.11 3.38 0.06
TOTAL R-VALUE OF ROOF		4.43 m2 KW
For ventilation spaces, the ventilation should not be less than 0.5L/s m2		
Permissible R-Value		3.70 M2 KW
Water Pipe Insulation Internal dia. Of pipe	Component	R-Value
Hotwater pipes	Isowor Aeroflex 135mm dia Snap on Glasswool Pipe section insulation	1.00
TOTAL R-VALUE OF ROOF		1.00 m2 KW
All Exposed hot water pipes with a 60mm dia. Must be insulated with a minimum R-Value of 1.00 m2 KW		
All Exposed hot water pipes with a dia. Greater than 80 mm dia. Must be insulated with a Minimum R-Value of 1.5 m2 kw		



9125

SCHEMATIC DRAINAGE SECTION

NOTE: 100mm PVC PIPING 50mm VENT PIPE.

ALL COVER LEVELS TO BE A MIN. OF 76mm ABOVE
THE BOUNDARY COVER LEVEL (MH-5).

HOUSE FFL TO BE A MIN. OF 230mm ABOVE THE BOUNDARY
COVER LEVEL (MH-5)

ALL PIPING BELOW FOUNDATION & DRIVEWAY TO BE
ENCASED IN CONCRETE.

- All work to be carried out strictly in accordance with national building regulations and follow the local authority regulations.
- All work to be executed by a competent persons qualified for the specific trade.
- All materials and workmanship are to comply with the relevant S.A.B.S codes.
- No part of proposed building work to project beyond site boundary lines.
- The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS9001/ISO 9001, able to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their source, meet the requirements of the Specifications.
- The contractor shall in all aspects of the work comply with the provisions of the Occupational Health and Safety Act, 1993 (act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
- All portions of the works related to any service or consultant's information is to be done in accordance with National Building Regulations. All drainage and waterproofing of retaining structures to be in accordance with specialist's design and details. All retaining walls, slabs, roof designs and structural columns to eng.'s details.

- All glazing to doors & windows in excess to 1sqm or less than 500mm above above finished floor level to be shown as fire-rated glazing
 • safety glazed in accordance with national building regulations & as per sans 10400 parts B & N
- Insulation, lay isover aerolite 135mm thick non-combustable & class 1 fire index rating on ceiling ensuring light fitted thermal barrier between the beams. Cut around light fittings and trap with approved adhesive. Wrap isover aerolite around cold & hot water pipes using a cable tie @ 300mm c/c.

- Hot Water Cylinder as required by SANS 204 Part 4.5.2.
- Hot water services the client must note that a minimum of 50% by volume of annual hot water heating requirement shall be provided by means other than electrical resistance heating, by means not limited to heat pumps.

- Hot Water usage should be minimised and the system maintained in accordance with the requirements as per SAN 10252-1
 - A. Insulation to be protected against the effects of weather & sunlight.
 - B. Be able to withstand the temperatures within the piping
 - C. Achieve the minimum R-Value as per table 13 of SAN 204
- Edition 1

- Hot water vessel & cylinder to be insulated with material achieving a minimum R-value of 20. Insulating on vessels, cylinder, tanks & piping containing cooling water to be protected by a vapour barrier on the outside of the insulation.

- The pipe insulation requirements do not apply to space heating water pipe where
 1. Located within the space being heated where the piping is to provide the heating to that space.
 2. Encased within a concrete floor slab or masonry.
 3. These pipes comply with SANS 10252-1

- Piping to be insulated includes all flow & return piping within 1m of the connection to the heating or cooling system & pressure relief piping within 1m of the connection to the heating or cooling system .

- Length of pipe runs should be minimised where possible
- All dimensions and levels to be check onsite by all trades before work commences.any discrepancies are to be brought to the attention of the architect.

- Do not scale this drawing. Figured dimensions to be used, all dimensions are in millimeters unless otherwise stated.

- these drawings & designs are under cm architectural copy right & are the property of SMARTHOME SOLUTIONS . no part is to duplicated or replicated with out SMARTHOME SOLUTIONS written consent.

- The architect accepts no responsibility for errors resulting from misinterpretation of the drawings.

Redacted for portfolio purposes.
Confidential information removed

Sketch Type : GROUND STOREY PLAN, SITE PLAN, FIRST STOREY PLAN, SECTIONS, ELEVATIONS AND NOTE

Page	Scale	Date	Foot print House	m2 m2	DRG N
1 of 1	AS SHOWN	02/7/2020	ERF size Coverage	m2 %	